BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34781

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/22/2018-19, Date: 27.02.2019

Improvements roads and drains in Munigurappa Layout in ward no 07 Byatarayanapura in Kodigehalli Sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of P Vijaya Babu (NANDI ENTERPRISES..)		
				In Figures		In Words
1	576.45	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.143.Item No.19.1)	Cum	137.0	78973.65	Rupees One Hundred Thirty Seven Only
2	86.29	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8with OPC @ 180 kgs, using 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.13, It.4.3)	Cum	4000.0	345160.00	Rupees Four Thousand Only
3	200.36	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications. Seocifications No. KBS 4.1,4.6 (Page NO. 14, Item NO. 4.11)	Cum	5000.0	1001800.00	Rupees Five Thousand Only
4	11.02	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.(Page No.18, Item No.4.46.2)	Tonne	75223.0	828957.46	Rupees Seventy Five Thousand Two Hundred Twenty Three Only
5	1644	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.(Page No.16, Item NO.4.32)	Sqm	483.0	794052.00	Rupees Four Hundred Eighty Three Only
6	9.23	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. (Page No. 13. Item No. 4.6)	Cum	5747.0	53044.81	Rupees Five Thousand Seven Hundred Forty Seven Only
7	513.75	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete, 10cm thick (Item No.5.31.2, Pg No.25)	Sqm	900.0	462375.00	Rupees Nine Hundred Only

P. Vijaya Babu

Signature of the contractor

13/09

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of P Vijaya Babu (NANDI ENTERPRISES..) In Figures		In Words
8	513.75	KSRB 5-8.1: Providing one line dressing to granite stone slab/granite stone masonry as per specifications. (Item No.5.17, Pg No.26)	Sqm	700.0	359625.00	Rupees Seven Hundred Only
9	576.45	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	Cum	94.0	54186.30	Rupees Ninety Four Only
					3978174.22	

P. Vijaya Babu

Signature of the Contractor

Executive Engineer 13/09
Byarayanapura Division
BBMP, Bangalore - 92

13/09